

# ET Summit 2024

Presented by



# Gas Absorption Heat Pumps (GAHPs) in DHW Systems



Cristalle Mauleon  
Engineering Manager  
Lincus, Inc.

## Agenda

- Advantages of GAHPs
- Previous Work
- Field Study Screening and Design
- GAHP Installation
- Baseline & Post Data
- Follow On Work



# Advantages of GAHPs

## Reduced Energy Usage

GAHP can operate at >100% Efficiency. Overall DHW energy use decreased.

## Lower Emissions

Higher efficiency reduces energy consumption reducing emissions. Electric HPWH emissions fluctuate based on time of day.

## Underserved Communities

Reduction in energy usage = lower utility bills.

## Decarbonization

Potential for further reduction of emissions when carbon capture is incorporated.

# Previous Projects

In two (2) previous Emerging Technology Studies, a GAHP was installed and saved energy at two sites with existing gas-fired boilers with storage tanks.

## Equipment Efficiency (COP)

		Existing	Post with GAHP	
	NEEA Project in Salem, OR <sup>1</sup>	0.70	1.06	18% Natural Gas Savings
	TAF Project in Ontario, Canada <sup>2,3</sup>	0.54	1.14	

1. GAHP installed in a nursing home to augment space heating and DHW systems
2. GAHP installed in a multifamily building to augment space heating and DHW systems
3. TAF Study did not provide % natural gas savings

# California Gas Emerging Technology (GET) Analysis

Goal: Determine energy savings potential in California buildings<sup>1</sup>

Methodology:

- GAHP COP f(OAT) data extracted from NEEA field study
- Extract space heating loads from DEER eQuest prototypes<sup>2</sup>
- Modify DEER Water Heater Calculator<sup>2</sup> to include GAHP and space heating loads
- Building types selected based on how well DHW/space heating load matched GAHP capacity

Building Type/Application	Savings %	Cost-Effectiveness Indicator (Portfolio Goal = 1.25)
Assembly: DHW Only	31%	0.88
Small Office: DHW & Space Heating	31%	0.21
Nursing Home: DHW & Space Heating	26%	0.62

1. Study ET22SWG0002. Details on methodology can be found in final project report (see references slide for link)


2. These resources are California Energy Efficiency program specific modeling tools

# Initial Site Screening Criteria

## Site Selection Criteria (Manufacturer #1)

- Multifamily or hotel
- 70+ multifamily units on (1) DHW system
- Use monthly summer gas use – 900 therm minimum desired
- Mechanical room/boiler enclosure on ground floor
- Space for new HX & buffer tank
- Minimum 6ft x 9ft of space outside for mounting GAHP
- GAHP
  - Enough airflow
  - Not near a window

**Gas Usage History** (*Total Therms used*)




# Design Criteria

- Design Criteria
- 40-60% of peak load, retain existing boiler for peak load
- Control strategy; supply  $>135\text{F}$  or  $\leq 135\text{F}$
- GAHP Controls: Mfg provided or interface with existing system
- DHW recirculation
  - Pump VSD controls such that return temp  $<122\text{F}$ , OR
  - GAHP NOT integrated into recirculation loop



# Piping Schematic



## Installation Pictures



- Upper Left: Installed GAHP Unit
- Upper Right: Piping to and from HX (insulated per T24)
- Lower Left: GAHP DDC control
- Lower Right: New Concrete Pad

# Challenges

- Design:
  - No design support provided by mfg
  - Contractor struggled with HX size and buffer tank size
- Controls
  - Mfg has two controls
  - Contractor struggled to set up
- Site Specific Challenges
  - Water pressure regulator
  - Failed supply flow meter
  - Boiler #2 failure



(L) Low water pressure DHW system #1


(R) Failed supply flow meter DHW system #1

# Baseline




	DHW System #1	DHW System #2	Total
Total Measured Net Heat Output [Btu]	95,956,358	85,113,320	181,069,678
Total Measured Gas Energy Input [Btu]	164,866,793	123,139,675	288,006,467
Total Measured Gas + Electric Energy Input [Btu]	166,354,401	125,077,418	291,431,819
System COP <sub>Gas</sub>	0.58	0.69	<b>0.63</b>
System COP <sub>Gas+Electric</sub>	0.58	0.68	0.62
Data Period	10/14/23 – 12/15/23		

# Post-Installation - COPs





- GAHP COP does not regress well with OAT
- Not enough DHW load
  - No recirc
  - Summer
  - Gas bills include boiler inefficiencies



- GAHP COP regresses well with Net Heat Output (NHO)
- This is a proxy for GAHP continuous run time

# GAHP COPs by Run Time



### Findings:

- GAHP COPs reach **steady-state** after **20 min**
- Avg GAHP COP equals **condensing boiler** at **45 min**

Vacillation after 30 min due to pulsing meters combined with few data points. Expected to converge with more run times >30 min

# Post-Installation Energy Savings

Metric	Value
Post-Installation Net Heat Output [btu]	88,941,311
Theoretical Baseline Gas Use [btu]	141,176,685
Post-Installation Gas Use [btu]	130,262,062
Savings [btu]	10,914,622
Savings [therm]	109
% Savings	<b>8%</b>
Post-Installation Data Period	6/7/24 to 7/9/24

## Baseline

- 0.63 COP

## Post

- Two-Variable regression:  $f(\text{OAT} \ \& \ \text{NHO})$

## Notes:

Two-Variable regression Min Temp = 62.4°F

CZ2022 Min Temp = 39.0°

## Future Plans

- Incorporate recirculation load into GAHP
- Use indirect storage tank (IST) instead of plate and frame HX
- Modify controls with lower minimum IST temp
- Additional field studies: (1) more launched, (2) more in the pipeline
- Field Study #2 incorporating design engineering firm



**This project was conducted through the ICF implemented, SoCalGas administered California Statewide Gas Emerging Technologies Program.**

**The project report can be found on [cagastech.com](https://cagastech.com)  
For more information, contact [get@caenergyprograms.com](mailto:get@caenergyprograms.com)**

## **Cristalle Mauleon**

Engineering Manager

Lincus/GET

[cmauleon@lincus.com](mailto:cmauleon@lincus.com)



1. NEEA Study: *Robur Heat Pump Field Trial*. (<https://neea.org/resources/robur-heat-pump-field-trial>)
2. TAF Study: Gas Absorption Heat Pumps. Technology Assessment and Field Test Findings (<https://taf.ca/publications/gas-absorption-heat-pumps/>)
3. GET Studies
  1. ET22SWG0002: Evaluation of Emerging Water Heating Technologies. (<https://www.etcc-ca.com/reports/evaluation-emerging-water-heating-technologies>)
  2. ET22SWG008: Gas-Fired Heat Pump Water Heating & Combi System Pilot Phase 1. (<https://www.etcc-ca.com/reports/gas-fired-heat-pump-water-heating-combination-system-pilot-phase-1>)
  3. On-going: ET23SWG002: Gas-Fired Heat Pump Water Heating & Combination System Pilot – Phase 2F – Site #1. (<https://www.etcc-ca.com/reports/gas-fired-heat-pump-water-heating-phase-2f-site-1>)